

**BILL OF QUANTITIES**

BOQ-

Bill of Quantities

ITEM	DESCRIPTION	UNIT	QTY	Unit Price (Amount)	Amount (Pesos)
(1)	(2)	(3)	(4)	(5)	(6)
<b>I-</b>	<b>DIVERSION WORKS</b>				
1.	Temporary Works	l.s.	1.00		
	<i>Amount in words :</i> _____				
2.	Desilting Works w/ disposal of excavated mtl.	cu.m.	6,800.00		
	<i>Amount in words :</i> _____				
3.	Railings	l.s.	1.00		
	<i>Amount in words :</i> _____				
<b>II-</b>	<b>CANALIZATION</b>				
1.	Class "A" concrete	cu.m.	285.00		
	<i>Amount in words :</i> _____				
2.	Class "B" concrete	cu.m.	752.18		
	<i>Amount in words :</i> _____				
3.	Reinforcing Steel Bars				
a.	Furnishing	kgs.	51,859.09		
	<i>Amount in words :</i> _____				
b.	Installation	kgs.	51,859.09		
	<i>Amount in words :</i> _____				
4.	Gravel Blanket	cu.m.	258.49		
	<i>Amount in words :</i> _____				
5.	Excavation Works	cu.m.	1,178.92		
	<i>Amount in words :</i> _____				
6.	Backfilling Works	cu.m.	630.00		
	<i>Amount in words :</i> _____				
7.	Desilting Works w/ spreading & leveling of excavated mtl.	cu.m.	3,488.00		
	<i>Amount in words :</i> _____				
<b>III-</b>	<b>CANAL STRUCTURES</b>				
1.	Class "A" concrete w/ dewat.	cu.m.	31.61		

ITEM	DESCRIPTION	UNIT	QTY	Unit Price (Amount)	Amount (Pesos)
(1)	(2)	(3)	(4)	(5)	(6)
	<i>Amount in words :</i> _____				
2.	Class "A" concrete w/o dewat.	cu.m.	50.43		
	<i>Amount in words :</i> _____				
3.	Reinforcing Steel Bars				
a.	Furnishing	kgs.	3,855.60		
	<i>Amount in words :</i> _____				
b.	Installation	kgs.	3,855.60		
	<i>Amount in words :</i> _____				
4.	Gravel Blanket	cu.m.	18.45		
	<i>Amount in words :</i> _____				
5.	RCP-12"Ø	pcs.	8.00		
	<i>Amount in words :</i> _____				
6.	RCP-24"Ø	pcs.	19.00		
	<i>Amount in words :</i> _____				
7.	RCP-30"Ø	pcs.	45.00		
	<i>Amount in words :</i> _____				
8.	Grouted Riprap	cu.m.	13.68		
	<i>Amount in words :</i> _____				
9.	Structure Excavation w/ dewat.	cu.m.	291.93		
	<i>Amount in words :</i> _____				
10.	Structure Excavation w/o dewat.	cu.m.	163.82		
	<i>Amount in words :</i> _____				
11.	Structure Backfill - BH=5km.	cu.m.	270.64		
	<i>Amount in words :</i> _____				
<b>IV-</b>	<b>PROTECTION WORKS</b>				
1.	Class "A" concrete	cu.m.	205.66		
	<i>Amount in words :</i> _____				
2.	Reinforcing Steel Bars				
a.	Furnishing	kgs.	11,311.30		
	<i>Amount in words :</i> _____				
b.	Installation	kgs.	11,311.30		
	<i>Amount in words :</i> _____				
3.	Grouted Riprap	cu.m.	966.66		

ITEM	DESCRIPTION	UNIT	QTY	Unit Price (Amount)	Amount (Pesos)
(1)	(2)	(3)	(4)	(5)	(6)
	<i>Amount in words :</i> _____				
4.	ECC (BH=5km)	cu.m.	2,964.79		
	<i>Amount in words :</i> _____				
<b>V-</b>	<b>ACCESS ROAD / SERVICE ROAD</b>				
1.	Clearing & Grubbing	sq.m.	2,160.00		
	<i>Amount in words :</i> _____				
3.	Roack Excavation	cu.m.	1,200.00		
	<i>Amount in words :</i> _____				
4.	ECC (BH=5km)	cu.m.	5,000.00		
	<i>Amount in words :</i> _____				
5.	Road Surfacing	cu.m.	4,350.00		
	<i>Amount in words :</i> _____				
	<b>Total</b>				
	<b>In Words</b>				

Submitted by:

\_\_\_\_\_  
Name of Representative of the Bidder

\_\_\_\_\_  
Position

\_\_\_\_\_  
Date

\_\_\_\_\_  
Name of the Bidder